

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division,  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt

County. Sec. 11 Twp. 27 Rge. 13 (E) X (W)

Location as "NE/CNW/SW" or footage from lines C 1/2 NE NE  
Lease Owner Samuel Greenberg, d/b/a Bulldog Pipe & Supply Co

Lease Name Kuryan Well No. 2  
Office Address Post Office Box 1153, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed 7-18-40 19

Application for plugging filed March 2, 1966 19

Application for plugging approved March 3, 1966 19

Plugging commenced March 3 19 66

Plugging completed March 16 19 66

Reason for abandonment of well or producing formation No longer commercially productive

If a producing well is abandoned, date of last production Unknown 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving, Pratt, Kans.

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	360'	
				5 - 1/2"	4289	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled back in the 5 1/2 with gravel and dumped 5 sacks of cement. Shot pipe off at 3229.05'. Pulled pipe and mudded hole to 300'. Set rock bridge and dumped 5 sacks of cement. After cement set, bailed hole and finished filling hole with ready-mix cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 18 1966

Name of Plugging Contractor Bert Self (If additional description is necessary, use BACK of this sheet)  
Address Hutchinson, Kans.

STATE OF Kans. COUNTY OF Reno, ss. \_\_\_\_\_ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 66  
October 15, 1966 My commission expires \_\_\_\_\_  
Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg., Wichita, Kansas.


COPY

ATLANTIC REFINING CO.  
Runyan No. 2

SEC. 11 T. 27 R. 13W.  
CE 1/2 NE NE

Total Depth. 4295  
Compt. 6-12-40 Comp. 7-13-40  
Shot or Treated. 5 qts 4292-4296. 7-8-40  
Contractor. Bodine Drilg. Co.  
Issued. 8-24-40

County Pratt.



CASING. Rotary with cable tool completion.

10 3/4" 360'  
5 1/2" 4289'

Elevation.

Production. Pot. 1568 B.  
Depthograph.

Figures Indicate Bottom of Formations.

surface clay and sand	70	sdv lime	3440
sand	100	lime	3470
shale	225	lime and shalo	3485
red bed	725	red rock and shalo	3510
anhydrite	775	lime	3520
red bed and shale	825	shale sdv	3560
shale	1060	shale	3630
shale and lime	1130	lime	3655
salt	1260	shale	3780
lime and shale	1290	lime	3850
shale and shells	1425	shale and lime	3869
shale	1605	chorty lime	3890
shale and shells	1840	lime	4095
lime	1940	shale	4130
sand and lime	2055	lime	4155
sticky shale	2130	shalo	4200
lime	2135	chat	4227
shale	2205	shalo and lime	4245
lime	2350	chorty shale and lime	4283
shale	2375	shalo	4289
lime sdv	2390	sand	4295
lime	2455	Total D pth.	
lime and shale	2540		
shale	2580		
lime	2605		
shalo and lime	2720		
shalo	2800		
lime broken	2810		
shalo, lime	2905		
shalo	3045		
broken lime	3115		
shalo	3225		
lime	3400		

RECEIVED  
STATE CORPORATION COMMISSION

MAR 3 1966

CONSERVATION DIVISION  
Wichita, Kansas