


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pratt County. Sec. 11 Twp. 29 Rge. 13 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines S/2 NE-NW  
Lease Owner Kansas Oil Field Supply Co., Inc.  
Lease Name Luders Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 6-10-57 19\_\_\_\_  
Application for plugging approved 6-10-57 19\_\_\_\_  
Plugging commenced 6-28-57 19\_\_\_\_  
Plugging completed 7-2-57 19\_\_\_\_  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4317 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	245'	none
				5 1/2	4301 1/2	3055'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4309', found hole open, filled w/sand to 4290' and ran 5 sacks cement. Pulled pipe. Halliburton pumped 25 sacks of mud and 80 sacks of cement.

Plugging completed

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. [Signature]  
420 West Douglas, Wichita  
(Address)

SUBSCRIBED AND SWORN TO before me this 3 rd day of July, 19 57

My commission expires 9-27-58

Thomas V. Duggin  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 11 T 27 R 13W  
BOOK PAGE 18 LINE 41

JUL 13 1957  
CONSERVATION DIVISION  
Wichita, Kansas


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- LINDSLEY DRIG. CO.  
Farm- Luders No. 2

SEC. 11 T. 27 R. 13T  
NW SE NE

Total Depth. 4324  
Comm. 7-21-51 Comp. 8-8-51  
Shot or Treated.  
Contractor. Lindsley Drlg. Co.  
Issued. 10-6-51

County Pratt  
KANSAS



Elevation. 1923

Production. Pmp. 25 bbls.

Figures Indicate Bottom of Formations.

sand, shale & shells	140
red bed, shale	245
cement	251
red bed & shells	717
anhydrite	750
shale & shells	1785
lime & shale	2670
shale	2965
lime & shale	3925
lime	3995
lime & shale	4095
lime	4120
lime & shale	4160
lime broken	4215
lime & shale	4222
lime & chert	4280
shale, chert & lime	4302½
shale, chert & lime	4324
Total Depth	

Scout Tops:	
Brown Lime	3746
Lansing-K.C.	3764
Miss.	4144
Kinderhook	4176
Viola	4194
Simpson Shale	4284

PLUGGING  
FILE SEC. 11 T. 27 R. 13W  
BOOK PAGE 18 LINE 41

RECEIVED  
STATE CORPORATION COMMISSION

JUN 13 1957

CONSERVATION DIVISION  
Wichita, Kansas