


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Pratt County. Sec. 11 Twp. 27 Rge. 13 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NE SE
Lease Owner Robt. K. Lindsley, et al
Lease Name Minnie Tritsch Well No. 1
Office Address 1012-13 Union National Bank Building, Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 11, 1952
Application for plugging filed June 15, 1952
Application for plugging approved June 27, 1952
Plugging commenced June 18, 1952
Plugging completed June 25, 1952
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4307 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				4-1/2"	4306'	2804'
				8-5/8"	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 4318' to 4280' and ran 4 sacks of cement. Bailed hole. Mudded hole to 260', set 10' rock bridge and ran 20 sacks of cement. Mudded hole to 40' and ran 10 sacks of cement on top. Plugging completed.


RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1952
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor West Supply
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, SS.
Robt. K. Lindsley (owner) of the above described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Robt. K. Lindsley
Union Nat'l Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of July, 1952.
Frances E. Halber
Notary Public.

My commission expires March 18, 1954



Tritsch #1

NW NE SE
Sec. 11-27S-13W
Pratt County, Kansas
Ele. 1913 DF
1910 Gr

Contractor: Lindsley Drilling Company
Started: 2/9/52 Finished 2/28/52

LOG

Surface sand, shells	0 - 190	
Red Bed, Shale, Shells	190 - 268	Set 8-5/8" @ 268' w/ 50 Sxs.
Sand	268 - 340	
Red Bed, Shells	340 - 1290	SLM @ 1000' - O.K.
Shells, Sand	1290 - 1560	SLM @ 1500' - O.K.
Shells & Shale	1560 - 1895	
Lime & Shale	1895 - 1990	
Lime & Shale	1990 - 2385	SLM @ 2000' - 1/2"
Lime	2385 - 2530	
Lime & Shale	2530 - 3080	SLM @ 3000' - O.K.
Lime & Shale	3080 - 3175	
Sandy Lime & Shale	3175 - 3250	
Chalky Lime-Shale	3250 - 3300	
Lime & Shale	3300 - 3425	
Chalky Lime	3425 - 3665	
Lime & Shale	3665 - 3818	- Strapped Pipe
Lime & Shale	3818 - 4270	
Viola-Lime & Shale-Chert	4270 - 4279	
Viola Lime -Chert - Shale	4279 - 4285	
Chert, Lime & Shale	4285 - 4299	
Chert-Simpson Sand	4299 - 4307	
Total Depth	4307	4 1/2" @ 4306' w/ 150 Sx.

TOPS:

Heebner	3577'
Brown Lansing	3742'
Landing	3766'
Base Kansas City	4098'
Mississippi	4173'
Kinderhook	4195'
Viola	4222'
Upper Viola Chert	4222 - 4234'
Lower Viola Chert	4253 - 4290'
Simpson	4295'
Simpson Sand	4304'
Rotary Total Depth	4307'

STATE OF KANSAS

COUNTY OF SEDGWICK

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1952
CONSERVATION DIVISION

I, Robt. K. Lindsley, do hereby certify that the above is a true and accurate log of the Tritsch well #1, located NW NE SE in Section 11, 27S-13W, Pratt County, Kansas.

Robt. K. Lindsley

Robt. K. Lindsley, Partner
Lindsley Drilling Company

Subscribed to and sworn before me this 18th day of March, 1952.

Vivian A. McKenzie

Notary Public

My Commission Expires September 18, 1952.

