

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pratt County, Sec. 14 Twp. 27 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE/4 NW/4 NW/4

Lease Owner Transit Corporation & Davis Bros.

Lease Name Rolfe Well No. 1

Office Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-29-52

Application for plugging filed 8-29-52

Application for plugging approved 8-29-52

Plugging commenced 8-29-52

Plugging completed 8-29-52

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4482 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	266	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 240', set plug and cemented with 20 sacks cement. Filled hole with heavy drilling mud to 35', set plug and cemented to bottom of cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 - 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation

Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

L. J. Kruse (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. J. Kruse*

Oklahoma City, Oklahoma

(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of September, 19 52

My commission expires October 24, 1955 *Lillian Wright* Notary Public.

PLUGGING
FILE SEC 14 T 27 R 13
BOX PAGE 46 LINE 16

TRANSIT CORPORATION & DAVIS BROS.

NE/4 NW/4 NW/4 Sec. 14-27S-13W

Pratt County, Kansas

ROLF NO. 1

<u>FORMATIONS</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	90	
Sand	90	105	
Sand & Shale	105	254	
Shale & Shells	254	748	
Anhydrite	748	780	
Shale & Shells	780	1440	
Salt & Shale	1440	1550	
Shale & Shells	1550	1840	
Lime	1840	1955	
Lime & Shale	1955	2260	
Lime	2260	2390	
Lime & Shale	2390	2605	
Shale & Lime	2605	2985	
Lime & Shale	2985	3465	
Lime	3465	3530	
Broken Lime	3530	3603	
Lime & Shale	3603	3655	
Sandy Shale	3655	3675	
Shale	3675	3728	
Lime & Shale	3728	3775	
Shale & Lime	3775	3818	
Lime	3818	4244	
Viola Lime	4244	4260	
Lime & Chert	4260	4290	
Lime	4290	4294	
Lime & Chert	4294	4349	
Lime Chert & Sand	4349	4364	
Sand	4364	4367	
Sand & Shale	4367	4387	
Shale & Lime	4387	4430	
Lime	4430	4482	

Total Depth 4482'

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

PLUGGING
 FILE SEC: 14 27 N 13W
 BOOK PAGE: 41 LINE: 6

TRANSIT CORPORATION

By: L. J. Kruse
 L. J. Kruse
 Ass't Secretary

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 5 1952
 CONSERVATION DIVISION
 Wichita, Kansas

Subscribed and sworn to before me this 4th day of September, 1952.

My Commission Expires: Oct. 24, 1955

William W. Winkler
 Notary Public