

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-151-21592-DD-01

API NUMBER Driller date: 3-20-85

LEASE NAME L.E. Studer

WELL NUMBER 1 OWWO

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 8 TWP. 24S RGE. 12 ~~XX~~ or (W)

COUNTY Pratt

Date Well Completed 1-22-86

Plugging Commenced 6-14-90

Plugging Completed 6-19-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Studer Oil Co.

ADDRESS P.O. Box 925 Pratt, Ks. 67124

PHONE# (316) 672-7572 OPERATORS LICENSE NO. 9582

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 18, 1990 (date)

by Steve Durant--Steve Pfeifer on location. (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached?

Producing Formation Mississippian Depth to Top Bottom T.D. 4480

Show depth and thickness of all water, oil and gas formations. Perfs: 4140-60 PBTD 4177'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	287	10 3/4	287	0
				4 1/2		52 jts. of casing.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Dumped sand to 50' above perfs and 4 sx. cement. Cut and pulled 52 jts. of 4 1/2 "
casing. Top hole plug: 6-19-90: 400# hulls, 15 sx. gel, 60 sx. cement, 13 sx. gel,
100# hulls, 10 3/4 wiper plug, 175 sx. cement on top. 60-40 poz, 6% gel. Max. pressure
125#, ISIP 50#
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124 STATE


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Studer Oil Co. JUN 28 1990

STATE OF Kansas COUNTY OF Pratt

Judy Berry

plugging contractor
 (Employee ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.



(Signature) Judy Berry

(Address) Box 847 Pratt, Ks.

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 90

Dorothy M. Ferguson
 Notary Public
 My Commission Expires: February 6, 1993