

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-151-21831-00-00

LEASE NAME Dikeman

WELL NUMBER 1

415' Ft. from S Section Line

1130' Ft. from E Section Line

SEC. 5 TWP. 27 SRGE 12W (E) or (W)

COUNTY Pratt

Date Well Completed 5-14-87

Plugging Commenced 9-14-93

Plugging Completed 9-20-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Deutsch Oil Company

ADDRESS 107 N. Market Su. 1115 Wichita, Kansas

PHONE# (316) 267-7551 OPERATORS LICENSE NO. 3180

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-27-93 (date)

by Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 4121 Bottom 4155 T.O. 4380

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	sand/lm	0	357	8 5/8	357	None
Production	lm	0	4380	4 1/2	4380	1999'

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 24 1993  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set  
Fill sand from td to 3868 ft. Set 4 sx cement plug at 3868  
Pump 3 sx. hulls, 10 gel, 50 sx. cement (60/40 poz. 6% gel) 10 gel,  
1 sx. hulls, wiper plug and 100 sx. cement (60/40 poz. 6% gel) down  
8 5/8" surface casing

Name of Plugging Contractor DS&W Well Servicing License No. 6901

Address Clafin, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Deutsch Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Kent Deutsch (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 107 N. Market, Su. 1115  
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 24 day of Nov., 1993

[Signature]  
Notary Public

My Commission Expires: 7/1/97



DRILLER'S WELL LOG

DATE COMMENCED: April 17, 1987  
DATE COMPLETED: April 26, 1987

Deutsch Oil Company  
DIKEMAN #1  
85' N & 140W of SW SE SE  
Sec, 5, T27S, R12W  
Pratt County, Ks.

ELEVATION: 1861 K.B.

0 - 629' Surface Soil, Sand, Clay,  
Red Bed  
629 - 654' Anhydrite  
654 - 3492' Shale & Lime  
3492 - 3496' Shale  
3496 - 3510' Lime & Shale  
3510 - 3532' Lime  
3532 - 3669' Shale  
3669 - 3681' Lime & Shale  
3681 - 4029' Lime  
4029 - 4120' Shale & Lime  
4120 - 4240' Chert & Lime  
4240 - 4334' Chert  
4334 - 4342' Shale  
4342 - 4380' Sand  
4380' RTD

FORMATION DATA

Anhydrite 629'  
Heebner 3492'  
Toronto 3510'  
Douglas 3532'  
Br. Lime 3669'  
Kansas City 3681'  
Base K.C. 4029'  
Mississippi 4120'  
Viola 4240'  
Simpson Sh. 4334'  
Simpson Sd 4342'  
RTD 4380'

Surface Pipe: Set new  
8-5/8", 20# @357' w/200  
sacks 60/40pozmix 2% gel  
3% cc.

Production Pipe: Set used  
4 1/2", 10 1/2# @ 4301' w/125  
sacks 60/40 pozmix 10%  
salt w/20 bbls. salt flush  
ahead.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 28 day of April 1987.



*Dorothy M. Hague*  
Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 26 1993

CONSERVATION DIVISION  
WICHITA, KS