

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,572-00-00

LEASE NAME Dikeman

WELL NUMBER "B" 1-5

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 5 TWP. 27 RGE. 12 (X) or (W)

COUNTY Pratt

Date Well Completed 3-23-85

Plugging Commenced 3-23-85

Plugging Completed 3-23-85

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P. O. Box 947, Pratt, Kansas 67124

PHONE#(316) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
		0	442'	8 5/8"	3-12-85	

APR 05 1985

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged well with 180 sxs 60/40 poz, 2% gel, 3% cc as follows: 4288'-50 sxs; 720'-50 sxs; 480'-40 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; mousehole-10 sxs; water well-5 sxs. Job by Halliburton. Complete at 8:30 p.m. on March 23, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 3rd day of April, 1985

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

Oilfield Services, Inc.

DRILLER'S WELL LOG

Dikeman "B" #1-5
 NW NE SW Sec. 5-27S-12W
 Pratt County, Kansas
 Commenced: 3-11-85
 Completed: 3-23-85
 API #15-151-21,572
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	456	Sand, Red Bed	Ran 10 joints (429') new, 24#, 8 5/8" surface casing. Set at 442' with 275 sxs Common, 3% cc, 2% gel. Job by Sun Cementing. Cement did circulate. Plug down at 1:45 a.m. on March 12, 1985.
456	1400	Red Bed	
1400	1812	Lime, Shale	
1812	2725	Shale	
2725	4350	Lime, Shale T.D.	

RTD 4350'

Plugged well with 180 sxs 60/40 poz, 2% gel, 3% cc as follows: 4288'-50 sxs; 720'-50 sxs; 480'-40 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; mousehole-10 sxs; water well- 5 sxs. Job by Halliburton. Complete at 8:30 p.m. on March 23, 1985. State Plugger was out of the Dodge City, Kansas Office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT



Mary L. Tjaden
 NOTARY PUBLIC

My Commission Expires:

3/22/88

RECEIVED
 STATE CORPORATION COMMISSION

APR 08 1985

CONSULTED