


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County. Sec. 5 Twp. 27S Rge. 12W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
N/2 NW NE

Lease Owner W. L. Kirkman, Inc.
Lease Name Schmitz Well No. 1
Office Address P.O. Box 18611, Wichita, Ks. 67207
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed March 26, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced March 26, 1980
Plugging completed March 26, 1980
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3690'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	467'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud from 3690 ft. (rotary total depth) to 450 ft. Set plug at 450 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 450 ft. to 270 ft. Set plug at 270 ft. and cemented with 40 sacks cement. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530

RECEIVED
APR 2 1980
CONSERVATION DIVISION
STATE CORPORATION COMMISSION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgewick
Dean Britting, Agent (Employee of owner) ~~xxx tower xxx operation~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 80



Elsie Willison Elsie Willison
Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY W. L. Kirkman, Inc.

SEC. 5 T. 27S R. 12W
 LOC. N/2 NW NE

FARM Schmitz NO. 1

COUNTY Pratt

ROTARY TOTAL DEPTH 3690'
 COMM. March 19, 1980 COMP. March 26, 1980
 CONTRACTOR H-30, Inc. (Rig No. 7)
 ISSUED March 31, 1980

CASING

10 3/4"
 8 5/8" Set at 467' cemented w/350 sxs cement
 5 1/2"
 4 1/2"

ELEVATION 1885' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Shale	838'
Shale, Shells and Lime	1435'
Shale and Lime	1785'
Lime and Shale	1896'
Shale and Lime	1956'
Lime and Shale	3233'
Lime	3374'
Lime and Shale	3690'
Rotary Total Depth	3690'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

RECEIVED
 CONSERVATION COMMISSION
 APR - 2 1980
 CONSERVATION DIVISION
 Topeka, Kansas

State of Kansas)
 County of Sedgwick) ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 31st. day of March, 1980.

My Commission Expires:
 July 25, 1982

Elsie Willison
 Elsie Willison - Notary Public

