

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas


WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Pratt County Sec. 5 Twp. 27 Rge. 12 (E) W (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NE
Lease Owner Hollow Drilling Company, Inc.
Lease Name Brown Well No. 1
Office Address Inman, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 22 1942
Application for plugging filed October 22 1942
Application for plugging approved October 22 1942
Plugging commenced 2:45 P.M. October 22 1942
Plugging completed 12:45 P.M. October 22 1942
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander
Producing formation None Depth to top Bottom Total Depth of Well 4426 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Sand	Water	58	145	8 5/8	464	None
Kansas City	Water	3690	4081	None	None	None
Miss Line	"	4131	4250	"	"	"
Viola	"	4258	4310	"	"	"
Simpson	"	4310	4396	"	"	"
Arbuckle	"	4396	4426	"	"	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud from 4426' to 300'--Wood plug and 15 sx cement plug placed at 300' - 265'

Hole filled with heavy mud from 265' to 26'--Wood plug placed at 26' and hole filled with cement to base of cellar 6'

Mud and cement on lower bridge placed in hole through drill pipe.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Hollow Drilling Company, Inc.
Address Inman, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.

Walter B. Hollow (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God


(Signature)

Inman, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October 1942

My commission expires 9-14-46

19-4174



Hattie M. Brown No. 1 "A" Well

SW SE NE 5-27-12w

(330 Ft. from South line-990 ft. from East line)

Pratt County, Kansas

Contractor: Hollow Drilling Company, Inc.
Inman, Kansas

Elevation 1860

Date Commenced: Sept. 28, 1942


Date Completed: Oct. 22, 1942

Tools: Rotary Drilling Tools

	Log
0	10 Cellar
10	22 Surface Sandy
22	58 Clay
58	75 Sand
75	110 Clay
110	145 Sandy
145	180 Clay
180	225 Shale
225	643 Red Bed
643	680 Andydrite
680	1050 Red Rock Shale & Shells
1050	1150 Red & Blue Shale & Lime Shells
1150	1350 Salt
1350	1738 Shale & Lime Shells
1738	1825 Lime
1825	1975 Shale & Lime
1975	2058 Lime & Shale Brakes
2058	2120 Lime
2120	2158 Sandy Shale & Lime
2158	2270 Shale & Broken Lime
2270	2380 Lime & Shale
2380	2400 Sandy Shale
2400	2525 Shale & Lime Shells
2525	2678 Lime & Shale
2678	2708 Sandy Shale
2708	2720 Broken Sandy Lime
2720	2780 Shale & Shells
2780	2800 Shale
2800	2845 Lime
2845	2888 Shale
2888	2955 Lime
2955	2980 Shale & Broken Lime
2980	3012 Lime
3012	3092 Lime & Shale
3092	3180 Shale
3180	3500 Lime
3500	3525 Shale
3525	3563 Lime
3563	3609 Lime & Shale
3609	3644 Lime
3644	3692 Shale
3692	3843 Lime
3843	3852 Chert & Lime
3852	4013 Lime
4013	4080 Lime & Shale
4080	4096 Chert & Lime
4096	4108 Lime
4108	4132 Shale & Lime
4132	4168 Chert
4168	4192 Shale
4192	4205 Cert & Lime
4205	4207 Shale
4207	4230 Chert & Lime
4230	4258 Lime & Shale
4258	4296 Chert
4296	4337 Chert & Shale
4337	4356 Sand
4356	4396 Shale
4396	4426 Arbuckle Lime

Data
2058 T. Ft. Riley
2190 B. Florence Flint
3160 T. Topeka
3690 T. Lansing
4081 T. Conglomerate
4131 T. Mississippi Lime
4258 T. Viola
4301-4310 Crystalline White Viola Lime
4310 T. SimpsoneShale
4396 T. Arbuckle
Note: All Measurements Deduct 2 Ft. from Derrick Floor.

464 ft. Surface Pipe 8 5/8



I, W. B. Hollow, Hereby Certify that the above and foregoing is a true and accurate copy of the log of the Brown "A" No. 1 well located in the SW SE NE 5-27-12s, Pratt County, Kansas.

W. B. Hollow

Dry--Plugged and Abandoned.

