

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-20,401-00-00

LEASE NAME Maas

WELL NUMBER C-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section Lin

         Ft. from E Section Lin

SEC. 16 TWP. 27 RGE. 12 W or (4)

COUNTY Pratt

Date Well Completed 7-16-77

Plugging Commenced 8-4-92

Plugging Completed 9:00 AM

LEASE OPERATOR Great Bend Casing Pullers, Inc.

ADDRESS P.O. Box 251, Great Bend, Ks 67530

PHONE# (316) 793-9711 OPERATORS LICENSE NO. 4635

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-4-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?         

Producing Formation Ind Cv Depth to Top 2673 Bottom 2679 T.D. 2740

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	338	0
				4 1/2	2740	1851

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from          feet to          feet each.  
Bottom plug: Sand to 2620 & bailed 4 sx Cement.

Top plug: Pumped 3 Hulls, 10 Gel, 50 sx Cement, 10 sx Gel, 100 lb Hulls, 100 sx Cement (60/40 6% Gel). Had maximum 250 lbs & shut in of 100 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Bend Casing Pullers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator) or (Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed. The same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 5 day of August, 1992



Anna K. Burke  
Notary Public

RECEIVED  
CORPORATION COMMISSION  
Wichita, Kansas