


15-151-20360-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County. Sec. 16 Twp. 27S Rge. 12W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
SE SW SE
Lease Owner Hummon Oil Corporation
Lease Name Johnson Well No. 1
Office Address 400 One Main Place, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Gas
Date Well completed Feb 1 19 77
Application for plugging filed 3-4- 19 81
Application for plugging approved 3-5 19 81
Plugging commenced 4-14 19 81
Plugging completed 4-21-81 - 1:30 p.m. 19 81
Reason for abandonment of well or producing formation _____

Dry
If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2900
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				12 3/4	157	None
				4 1/2	2786	2335

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Plug back in hole at 2738

Sand from 2738 to 2625
4 sacks cement from 2625 to 2600

Allied - Pumped in 15 sacks Jell - 800 lb.s Hull - 10 sacks Jell
225 sacks cement 50-50 POZ - 4% Jell - 3% C.C.

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation 583

STATE OF Kansas COUNTY OF Barber, ss.
Elmo R. Morgenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Morgenstern
Medicine Lodge, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 1981

Jessie Hamerton
Notary Public.

My commission expires April 4, 1982

ROTARY DRILLERS' LOG

OPERATOR: Hummon Oil Company
 1725 KSB & T Building
 Wichita, Kansas 67202

DRILLING COMMENCED: 1 Feb. 1977

CONTRACTOR: Graves Drilling Co., Inc.
 910 Union Center
 Wichita, Kansas 67202

DRILLING COMPLETED: 6 Feb. 1977

CASING RECORD: 7 Jts. 157' of used 12-3/4"
 cemented with 225 sacks;
 71 Jts. 2786' of new 4-1/2"
 cemented with 100 sacks

LOCATION: Johnson No. 1
 SE SW SE
 Section 16-27S-12W
 Pratt County, Kansas

0 - 157	Sand & red bed
157 - 193	Red bed
193 - 1787	Red bed & shale
1787 - 1998	Shale & lime
1998 - 2270	Shale
2270 - 2572	Shale & lime
2572 - 2694	Lime & shale
2694 - 2761	Shale & lime
2761 - 2900	Lime & shale
2900	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

RECEIVED
 MAR 1981
 CONSERVATION DIVISION
 WICHITA, KANSAS

By Courtney M. Graves
 Secretary-Treasurer

STATE OF KANSAS)
)
 SEDGWICK COUNTY) SS:

Subscribed and sworn to before me, a Notary Public, this 15th day of February, 1977

My commission expires: 2 February 1980

Courtney M. Graves
 Courtney M. Graves Notary Public



*Types set by
 State Dept. of Geology
 Kansas Geological Survey
 Kansas Geological Society*