


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 11 Twp. 27 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SE NW

Lease Owner Amerada Petroleum Corp.

Lease Name J. E. Whitman Well No. 1

Office Address 614 Orpheum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-2 1953

Application for plugging filed 6-2 1953

Application for plugging approved (oral) 6-2 1953

Plugging commenced 6-2 1953

Plugging completed 6-2 1953

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4636 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	715	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 300'
Set plug at 300'
Dumped 1 sack cottonseed hulls on top of plug
Mixed and dumped 30 sacks cement
Filled hole with heavy mud to 40'
Set Plug at 40'
Dumped 1 sack cottonseed hulls on top of plug
Mixed and dumped 10 sacks cement filling hole to top of 8-5/8" casing
in bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Survey Drilling Co.

Address Box 324, Dallas, Texas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. J. Stone (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. J. Stone
614 Orpheum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1953,

R. P. Kendrick
Notary Public.

My commission expires October 4, 1956



RECEIVED
 STATE CORPORATION COMMISSION
 JUN 10 1953
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLER'S LOG

Company: Amerada Petroleum Corporation NW SW NW
 Farm: J. E. Whitman Well No. 1 Section 20-27S-12W
 Total Depth 4636 County: Pratt, Kansas
 Comm: 5-5-53 Comp: 6-2-53
 Contractor: Survey Drilling Company
 Casing: 8-5/8" - 715' - cemented with 400 sks
 Elevation: 1876 Derrick Floor
 Production: Dry

Figures below indicate bottom of formations:

Shale and sandy shale	0 -	605
Anhydrite		753
Shale		1250
Salt, shale, and Anhydrite		1930
Lime and shale		2280
Broken lime and shale		2420
Lime and shale		2690
Shale, sandy shale and lime		2880
Lime and shale		3080
Shale and lime		3172
Lime and shale		3581
Shale, sandy shale and sand		3698
Lime		4060
Lime and shale		4161
Lime and cherty lime		4320
Shale		4350
Lime and cherty lime		4453
Sand and dolomitic sandy shale		4538
Dolomite		4636 (R.T.D.)

This is to certify that the above information is, to the best of our knowledge true and correct.

Amerada Petroleum Corporation

By: W M Kennington

SUBSCRIBED AND SWORN to before me this 9 day of June, 1953

My commission expires October 4, 1956

J. P. Hendrick
Notary Public

PLUGGING
 FILE SEC. 11.7-27R-12W
 BOOK PAGE 105-116-13