

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,613

LEASE NAME Barker #1

WELL NUMBER #1

SPOT LOCATION SW NE SW

SEC. 26 TWP. 27 RGE. 12 ~~XXXX~~ (W)

COUNTY Pratt

Date Well Completed 7-4-85

11:45 PM,

Plugging Commenced 7-3-85

1:30 AM,

Plugging Completed 7-4-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Zenith Drilling Corporation

ADDRESS 505 Fourth Financial Center
Wichita, Kansas 67202

PHONE # (316) 265-6697 OPERATORS LICENSE NO. 5141

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4133'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8'	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud plugged through open ended drill pipe, circ. before plugged 50 sacks at 870'; 60 sacks at 270'; 3/4 sack hulls, plug and 20 sacks at 40'; circ. 15 sacks in rathole with joint of pipe. Used 60/40 Pozmix, plus 4% gel (total of 6%), plus 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579


STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) Richard L. Mead
Richard L. Mead, President

(Address) P. O. Box 129, Sterling, Kansas 67579



12 1985
JUL 12 - 85
SUBSCRIBED AND SWORN TO before me this 8 day of July, 1985
Wichita, Kansas

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-89

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - BARKER #1
Located: SW NE SW, Section 26-27S-12W, Pratt County, Kansas

OWNER: Zenith Drilling Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 22, 1985
COMPLETED: July 4, 1985

TOTAL DEPTH: 4133'

LOG

0 - 255 Surface Soil, Sand
and Red Bed
255 - 600 Shale, Sand, Red Bed
600 - 610 Anhydrite
610 - 1370 Shale
1370 - 3810 Lime and Shale
3810 - 3830 Lime
3830 - 3900 Lime and Shale
3900 - 3995 Lime
3995 - 4078 Lime and Chert
4078 - 4133 Lime

CASING RECORD

Ran 6 joints new 13 3/8", 54.5# casing.
239.69' pipe set at 252' K.B. Cemented
with 250 sacks 60/40 Pozmix, 3% cc.
Plug down at 3:45 PM, 6-22-85, by
Howco.

Plugged.

NOTE: Drilled 12 1/4" hole
to 970'. Deviation Survey 5°.
Cemented from 970' to 255' with
550 sacks Class A Common with
5% sand and 3% cc. Job complete
at 2:00 AM, 6-25-85, by
Halliburton.

Deviation Surveys: 1° at 300'
5° at 970'
3/8° at 300'
1° at 400'
1° at 472'
1° at 534'
1° at 598'
1/2° at 659'
1/2° at 814'
3/4° at 1024'
3/4° at 2148'
1 3/4° at 3810'
7/8° at 4133'

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1985

CONSERVATION DIVISION
Wichita, Kansas