

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,542-00-00

LEASE NAME -Carver

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 24 TWP. 27 RGE. 12 (X) or (W)

COUNTY Pratt

Date Well Completed 1-14-85

Plugging Commenced 1-14-85

Plugging Completed 1-14-85

LEASE OPERATOR Mallonee-Warren, Ltd.

ADDRESS 302 N. Rock Rd-Suite 206, Wichita, Ks. 67206

PHONE#(316) 687-5115 OPERATORS LICENSE NO. 9092

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4540

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
						FEB 05 1985

CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged well with 125 sxs 60/40 poz, 2% gel, 3% cc as follows: 660'-40 sxs; 330'-50 sxs; 40'-plug and 15 sxs; rathole-10 sxs; mousehole-15 sxs. Job by Halliburton. Complete at 5:45 p.m. on January 14, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Ks. 67124

SUBSCRIBED AND SWORN TO before me this 1st day of February, 1985



Mary L. Tjaden  
Notary Public

My Commission Expires: 3/22/88



# Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

## DRILLER'S WELL LOG

Carver #1  
 NE SW SE Sec. 24-27S-12W  
 Pratt County, Kansas  
 Commenced: 1-2-85  
 Completed: 1-14-85  
 API #15-151-21,542  
 Operator: Mallonee-Warren, Ltd.

Depth		Formation	Remarks
From	To		
0	309	Sand, Red Bed	Ran 7 joints (281.25') new, 61#, 8rd, 13 3/8" surface pipe. Set at 291' with 300 sxs 60/40 poz, 2% gel, 3% cc. Job by Halliburton. Cement did circulate. Plug down at 7:15 a.m. on January 3, 1985.
309	1906	Red Bed	
1906	2592	Sand, Shale	
2592	2852	Shale	
2852	4540	Lime, Shale	
		T.D.	

RTD 4540'

Plugged well with 125 sxs 60/40 poz, 2% gel, 3% cc as follows: 660'-40 sxs; 330'-50 sxs; 40'-plug and 15 sxs; rathole-10 sxs; mousehole-15 sxs. Job by Halliburton. Complete at 5:45 p.m. on January 14, 1985. State Plugger was out of the Dodge City, Kansas office

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
 ARNIE LITTLE, VICE-PRESIDENT  
 STATE CORPORATION COMMISSION



*Mary L. Tjaden*  
 NOTARY PUBLIC FEB 05 1985

My Commission Expires:

3/22/88

CONSERVATION DIVISION  
 Wichita, Kansas