

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15151-26399-00-00

LEASE NAME Maas A #1

WELL NUMBER _____

SPOT LOCATION SW NE SW

SEC. 21 TWP. 27 RGE. 12 W (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 10/19/84

Plugging Completed 10/23/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D.R. Lauck Oil Co., Inc.

ADDRESS 221 S. Broadway, Suite 400, Wichita, Ks. 67202

PHONE # (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 2740'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	343'	none
				4 1/2"	2739'	2105'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped bottom with 30 sacks cement to 2500'. Shot pipe at 2312', & 2105'. Pulled 65 joints of pipe. Plugged well with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

RECEIVED

STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1984.



Deane Hoover
Notary Public

My Commission expires:

D. R. Lauck Oil Company, Inc. - Maas "A" #1
SW NE SW Sec. 21-27S-12W
Pratt County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
301 S. Broadway
Wichita, Kansas 67202

Commenced: July 22, 1977
Completed: July 27, 1977

Drillers Log

Sand	145
Red Bed	245
Sand	295
Red Bed	470
Shale & Shells	1890
Shale & Lime	2685
Lime	2690
Shale & Lime	2740 RTD

Casing: 342' 8-5/8" cemented with 275 sacks Common Cement,
2% Gel, 3% Calcium Chloride.
2739' 4-1/2" cemented with 75 sacks Salt Saturated
60-40 Pozmix Cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 07 1981

CONSERVATION DIVISION
Wichita, Kansas