

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR  
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Pratt County. Sec. 21 Twp. 27S Rge. (E) 21 (W) 17

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. Ctr. NW/4 NW/4 SE/4

Lease Owner Lion Oil Company

Lease Name Allen Well No. 1

Office Address P. O. Box 639, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-29 19 52

Application for plugging filed 6-26 19 52

Application for plugging approved 6-26 19 52

Plugging commenced 6-27 19 52

Plugging completed 7-2 19 52

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rivas

Producing formation Depth to top Bottom Total Depth of Well 4585 Feet

Show depth and thickness of all water, oil and gas formations. Plugged Back T.D. 3755'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	796'	None
				5-1/2"	4026'	2912'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole from 3755' to 3730' and ran 5 sacks of cement. Mudded hole to 315', set 15' rock bridge to 300' and ran 20 sacks of cement at 300'. Mudded hole to 40' and ran 10 sacks of cement. Plugging completed.

Plugging Contractor: West Supply Company  
Chase, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 10 1952  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Vernon Hayes  
Address P. O. Box 639  
Pratt, Kansas

STATE OF Kansas COUNTY OF Pratt, ss.  
Vernon Hayes (employee of owner)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Vernon Hayes*  
P. O. Box 639, Pratt, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 52

*Van Deibel*  
Notary Public.

My commission expires August 29, 1955

22-2625 2-48-15M

PLUGGING  
FILE SEC 21 T 27 R 18W  
BOOK PAGE 27 LINE 3

DRILLING LOG

LEASE: #1 Allen "A"

County: Pratt  
 Location: NW/4 NW/4 SE/4  
 Section: 21-27S-11W  
 Elevation: 1839' LP  
 1836' Gr.  
 1842' BB

Rotary Total Depth: 4585'  
 Commenced: 4-24-52  
 Completed: 5-16-52  
 Casing: 13" @ 207' w/75 sacks of cement.  
 8-5/8" @ 796' w/4 sacks of stratacrete cement  
 and 100 sacks of regular cement.  
 5 1/2" @ 4026' w/200 sacks of cement

CONTRACTOR: John Lindas Oil, Inc.  
 1316 Union National Bank Building  
 Wichita 2, Kansas

FIGURES INDICATE BOTTOM OF FORMATION

0	to	175	Sand and Shells
175		250	Shale
250		606	Red Bed
606		628	Anhydrite
628		635	Shale
635		796	Shale & Shells
796		960	Shale
960		1050	Salt & Shale
1050		1615	Shale & Shells
1615		2040	Lime
2040		2205	Broken Lime
2205		2825	Lime & Shale
2825		3085	Shale & Shells
3085		3287	Shale & Lime
3287		3415	Lime
3415		3510	Shale & Lime
3510		3575	Lime
3575		3720	Sand & Shale
3720		4167	Lime
4167		4210	Lime & Chert
4210		4237	Lime
4237		4271	Lime & Chert
4271		4304	Lime
4304		4355	Chert & Lime
4355		4400	Lime
4400		4425	Lime & Sand
4425		4457	Lime & Shale
4457		4585	Lime
		4585	TD

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SELWYCE )

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true and correct record of the well drilled by John Lindas Oil, Inc. at the location above described.

FILE NO. 21-27-11W-3  
 BOOK PAGE 27 LINE 3

*Edward W. Quinn*

Subscribed and sworn to before me, this 19th day of May, 1952.

INSERVATION DIVISION  
 Wichita, Kansas

My commission expires: March 24, 1955

*Agnes M. Quinn*  
 Notary Public