

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Pratt County, Sec. 32 Twp. 27S Rge. 12W (E) (W)  
 Location as "NE/CNW/SW" or footage from lines SE NE NE  
 Lease Owner Landes Exploration Co. and Sentinel Resources Corp.  
 Lease Name Lunt Well No. 1  
 Office Address P. O. Box 867, Magnolia, Arkansas 71753  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed December 14 19 69  
 Application for plugging filed December 14 19 69  
 Application for plugging approved December 14 19 69  
 Plugging commenced December 14 19 69  
 Plugging completed December 14 19 69  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman Justus, Box 71, Nickerson, Kansas  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4419 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	312'	10 3/4"	312'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug: 280'/35 sacks cement/1/2 sack hulls  
40'/15 sacks cement/1/2 sack hulls


RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 23 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Hellar Drilling Company, Inc.  
 Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
D. L. Hellar, President of Hellar Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, President  
339 Union Center Bldg., Wichita, Kansas 67202  
 (Address)

Subscribed and sworn to before me this 19th day of December, 19 69  
March 25, 1972



Catherine Darcey  
 Catherine Darcey Notary Public.

DRILLER'S LOG

COMPANY: Landes Exploration Co. and Sentinel Resources Corp.  
 P. O. Box 867, Magnolia, Arkansas 71753  
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202  
 LEASE: #1 Lunt  
 LOCATION: SE NE NE 32-27S-12W, Pratt County, Kansas  
 COMMENCED: December 1, 1969  
 COMPLETED: December 14, 1969  
 CASING: Set 10 3/4" Surface Casing @ 312'/250 sacks cement

0-45	Surface Soil & Sand
45-100	Sand
100-312	Sand & Red Bed
312-1025	Red Rocks & Red Bed
1025-1635	Shale & Shells
1635-1730	Shale & Lime
1730-2182	Lime & Shale
2182-2310	Shale & Lime
2310-2536	Lime & Shale
2536-2660	Shale & Lime
2660-2980	Lime & Shale
2980-3140	Shale & Lime
3140-3783	Lime & Shale
3783-4185	Lime
4185-4190	Miss.
4190-4248	Lime & Chert
4248-4265	Lime
4265-4322	Lime & Chert
4322-4370	Chert & Lime
4370-4378	Simpson shale & sand
4378-4383	Sand
4383-4419	Simpson
4419	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 23 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

D & A

STATE OF KANSAS        )  
                               )    SS  
 COUNTY OF SEDGWICK    )

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Lunt, located in SE NE NE 32-27S-12W, Pratt County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*  
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 19th day of December, 1969.



*Catherine Darcey*  
 Notary Public - Catherine Darcey

My Commission Expires: March 25, 1972.