


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

WELL PLUGGING RECORD

Pratt County. Sec. 29 Twp. 27S Rge. 12W ~~XXXX~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C - NE NE SW
Lease Owner K.R.M. Petroleum Corporation
Lease Name Bruce Well No. 1
Office Address 817 -17th. Street, Denver, Colorado 80201
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed February 13, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced February 13, 1980
Plugging completed February 13, 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4270'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	460	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4270 ft. (rotary total depth) to 450 ft. Set plug at 450 ft. and cemented with 40 sacks cement.

Filled hole with heavy rotary mud from 450 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4½ inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick

Dean Britting, Agent

(Employee of owner) or (owner) or (operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

200 No. Main, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 31st. day of March, 19 80

Elsie Willison

Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY K.R.M. Petroleum Corporation

SEC. 29 T. 27S. 12W

FARM Bruce

NO. 1

LOC. C - NE NE SW

COUNTY Pratt

ROTARY TOTAL DEPTH 4270'

COMM. February 3, 1980

COMP. February 13, 1980

CONTRACTOR H-30, Inc. (Rig # 3)

ISSUED March 31, 1980

CASING

10 3/4" Set at 460' cemented w/375 sxs cement
 8 5/8"
 5 1/2"
 4 1/2"

ELEVATION 1839' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	120'
Red Bed	461'
Red Bed and Shale	1663'
Shale, Lime and Chert	1315'
Lime and Shale	2080'
Shale and Lime	2290'
Lime and Shale	4060'
Lime	4218'
Lime and Shale	4270'
Rotary Total Depth	4270'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting

RECEIVED
 STATE CORPORATION COMMISSION
 APR - 1 1980
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas)
 County of Sedgwick) ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 31st. day of March, 1980.

My Commission Expires:

July 25, 1982

Elsie Willison - Notary Public