


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 28 Twp. 27 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. NW NE SW
Lease Owner Kern-Landes Expl. Co., Inc.
Lease Name ELMER Well No. 1
Office Address P.O. Box 699 Magnolia, Arkansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 4 1964
Application for plugging filed September 4 1964
Application for plugging approved September 4 (verbally) 1964
Plugging commenced September 4 1964
Plugging completed September 4 1964
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4510 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	277	8 5/8"	277	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 275 feet with

a plug and 25 sacks of cement at this point. Heavy mud to 40 feet with

a plug and 8 sacks of cement at this point. Two sacks of cement in

rat hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1964

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms Drilling Company
Address Box 488 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Allan Harms

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 488 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 1964

My commission expires January 22, 1966.

Helen E. Gearhart

Notary Public.

D R I L L E R S L O G

COMPANY: Kern-Landes Expl. Co., Inc.
 FARM: Elmer #1
 COMMENCED: August 17, 1964
 Elevation: 1815 KB

NW NE SW Section 28-27-12W
 Pratt County, Kansas
 COMPLETED: September 4, 1964

0 - 120 sand
 120 - 620 red bed
 620 - 645 anhydrite
 645 - 1620 shale & shells
 1620 - 3494 lime & shale
 3494 - 3500 Heebner
 3500 - 3533 lime
 3533 - 3575 shale
 3575 - 3679 shale & sand
 3679 - 4169 lime
 4169 - 4265 Mississippi
 4265 - 4274 lime
 4274 - 4304 shale
 4304 - 4361 lime & chert
 4361 - 4376 core
 4376 - 4384 core
 4384 - 4419 Simpson
 4419 - 4436 Simpson & shale
 4436 - 4490 shale
 4490 - 4510 Arbuckle
 4510 Total depth

SET 277 feet of 8 5/8 inch surface pipe. Cemented with 225 sacks of cement with 2% calcium chloride.

RAN electric log

DRY, plugged, and abandoned.


A F F I D A V I T

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, Allan Harms of the Harms Drilling Company being first duly sworn on oath state:
 I have knowledge of the facts, statements and matters herein contained and the same are true and correct.


 Allan Harms

Subscribed and sworn to before me this 15th day of September, 1964.


 Helen E. Gearhart - Notary Public

My commission expires: January 22, 1966.

RECEIVED
 STATE CORPORATION COMMISSION

SEP 16 1964

CONSERVATION DIVISION
 Wichita, Kansas