


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pratt County, Sec. 35 Twp. 27 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Tomlinson-Kathol, Inc.
Lease Name Barker Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/5/ 19 62
Plugging completed 1/8/ 19 62
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	400'	None
				4 1/2"	4187'	3885'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4046', sanded to 3995 and dumped 5 sacks of cement @ 3995' with dump bailer. Pulled 4 1/2" casing, bailed hole to 200' set 10' rock bridge to 190' and filled to base of cellar with 4 yards of ready-mix cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

FEB 9 1962

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Company (If additional description is necessary, use BACK of this sheet)
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Warren E. Tomlinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren E. Tomlinson
414 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 62

Esther Lamane
Notary Public.

My commission expires 1/19/65



WELL LOG

COMPANY: FALCON SEABOARD DRILLING COMPANY

Section 35-27S-12W

FARM: Shirk No. 1-B

Location - SE SE NE

TOTAL DEPTH: 4,501'

County - Pratt

COMM: 2-8-57. COMP: 3-4-57.

<u>CASING</u>		
16"	-	40'
10-3/4"	-	402'
8-5/8"	-	821'

<u>ELEVATION</u>	
D.F.	- 1762'
Gr.	- 1753'

DRILLER'S LOG

Red Bed, Gravel & Shale	0	270
Red Bed & Sand	270	572
Sand	572	612
Sand, Anhydrite & Shale	612	976
Shale & Shells	976	1079
Red Bed & Anhydrite	1079	1257
Red Bed, Anhydrite & Shale	1257	1564
Shale & Shells	1564	1881
Shale & Lime	1881	2498
Sand, Shale & Lime	2498	2628
Shale & Lime	2628	2852
Lime	2852	3310
Lime & Shale	3310	3502
Sand, Lime & Shale Stks.	3502	3620
Sdy. Lime & Shale Stks.	3620	3660
Lime	3660	3843
Lime & Shale	3843	3893
Sdy. Lime	3893	3959
Lime & Shale	3959	4063
Chert	4063	4117
Chert & Lime	4117	4142
Sdy. Lime & Shale	4142	4179
Shale & Lime	4179	4350
Shale, Lime & Sand	4350	4368
Shale & Sdy. Lime	4368	4400
Cherty Lime & Shale	4400	4446
Shale & Lime	4446	4470
Lime	4470	4501
Total Depth		4501

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 9 - 1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
FILE SEC. 35 T. 27 R. 12W
BOOK PAGE 145 LINE 38