


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pratt County. Sec. 35 Twp. 27 Rge. 12 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SE SE NE
Lease Owner Tomlinson-Kathol, Inc.
Lease Name Barker Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/5/ 19 62
Plugging completed 1/8/ 19 62
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	400'	None
				4 1/2"	4187'	3885'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4046', sanded to 3995 and
dumped 5 sacks of cement @ 3995' with dump
bailer. Pulled 4 1/2" casing, bailed hole to 200'
set 10' rock bridge to 190' and filled to base
of cellar with 4 yards of ready-mix cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1962

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Warren E. Tomlinson (employer or owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren E. Tomlinson
414 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of January, 19 62

My commission expires 1/19/65
Eather Lamore Notary Public.



DRILLERS LOG
TOMLINSON-KATHOL, INC.
1 BARKER
SE SE NE, SEC. 35-27-12W
PRATT COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced: 12/13/61
Completed: 12/15/61

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	300	Wash & Ream	
300	2420	Wash & Ream	
2420	4214	Washdown	

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Warren E. Tomlinson
Warren E. Tomlinson

State of Kansas)
)SS:
County of Sedgwick)

Subscribed and sworn to before me this 17th day of December, 1961.

Ethel Lamore
Notary Public

My Commission Expires: 1/19/65

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1962
CONSERVATION DIVISION
TOPEKA, KANSAS