

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A 15-151-20042-00-00

LEASE NAME BARKER B

WELL NUMBER 4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

990 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Emil E. Bowers

SEC. 35 TWP. 275 RGE. 12 (E or (W)

ADDRESS 125 No. Market, WICHITA, KS. 67202

COUNTY PRAATT

PHONE# (316) 262-6449 OPERATORS LICENSE NO. 5435

Date Well Completed 10-19-87

Character of Well Oil

Plugging Commenced 10-29-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-29-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation LANSING KC Depth to Top 3626 Bottom 3993 T.D. 4115

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LANS. KC	Oil	0	220	13 3/8	220	0
		0	316	8 7/8	316	0
		0	4104	4 1/2	4104	1250

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled w/ SAND to 3600' w/ 45# Cement, Pulled 1250' CASING, plugged hole w/ 45# HULLS, 100# SAX TRICITY MIX Cement by B.J.

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bowers Drilling Co., Inc. License No. NOV 1 9 1987 3235

Address 125 No. Market, Suite 1425, WICHITA, KS. CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Emil E. Bowers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Emil E. Bowers

(Address) Wichita, Kans.

SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 87

Judy C. Ridder RECEIVED
STATE CORPORATION COMMISSION

My Commission Expires:

JUDY C. RIDDER
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. 3/2/88

NOV 19 1987

Form CP-4
Revised 08-84
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY: Bowers Drilling Company, Inc.
CONTRACTOR: Bowers, Drilling Company, Inc.
FARM: Barker B#4
LOCATION: NW SW SE Section 35-27S-12W
Pratt County, Kansas
COMMENCED: 9-4-67
COMPLETED: 9-15-67
ELEVATION: 1775 Kelly Bushing

0 - 745	Red Bed	13-3/8" set @ 220' W/250 sx.
745 - 1610	Shale	8-5/8" set @ 316' W/350 sx/
1610 - 3773	Lime & Shale	
3773 - 4030	Lime	
4030 - 4115	Lime & Chert	4-1/2" set @ 4104' W/175 sx.
4115 -	T.D.	

LOG TOPS


Haebner	3421 -1641
Toronto	3438 -1663
Douglas Sand	3452 -1677
Brown Lime	3608 -1833
Lansing	3626 -1851
Base/Kansas City	3993 -2218
Marmaton	4019 -2244
Mississippian	4074 -2299
LTD	4115

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Barker B#4 located NW SW SE of Section 35-27S-12W Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.


Emil E. Bowers, President

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 26th day of September, 1967.


Elaine L. Winter, Notary Public

My Commission expires May 5, 1970.

RECEIVED
STATE CORPORATION COMMISSION

APR - 9 1967

CONSERVATION DIVISION
Wichita, Kansas