

API NUMBER N/A 15-151-2064D-DD-00

LEASE NAME BARKER "B"

WELL NUMBER 3

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

2640 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 35 TWP. 27S RGE. 12 (S) or (W)

COUNTY FRONT

Date Well Completed 10-3-67

Plugging Commenced 10-29-87

Plugging Completed 10-29-87

LEASE OPERATOR Bowers Drilling Co., Inc.

ADDRESS 125 No. Market, Wichita, Ks. 67202

PHONE# (316) 262-6449 OPERATORS LICENSE NO. 5435

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Lansing KC Depth to Top 3612 Bottom 3973 T.D. 4099

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LANS. KC	oil	0	164	13 3/8	164	0
		0	821	8 5/8	821	0
		0	4068	5 1/2	4068	1812

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

FILL WITH SAND TO 3500' w/ S&S Cement. Pulled 1812' casing, plugged w/ 4 S&S Hulls, 100 S&S Thrifty Mix Cement by B.I. 500# 51P.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bowers Drilling Co., Inc. License No. 5435

Address 125 No. Market, Suite 1425, WICHITA, KANSAS, 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss. NOV 19 1987

Emil E. Bowers (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Emil E. Bowers

(Address) Wichita, Kans.

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1987

Judy C. Ridder

My Commission Expires:

JUDY C. RIDDER  
 STATE NOTARY PUBLIC  
 SEDGWICK COUNTY, KANSAS  
 MY APPT. EXP. 3/2/88

Notary Public  
 STATE CORPORATION COMMISSION

NOV 19 1987 Form CP-4  
 Revised 08-84

WELL LOG

**COMPANY:** Bowers Drilling Company, Inc.  
**CONTRACTOR:** Bowers Drilling Company, Inc.  
**FARM:** Barker B#3  
**LOCATION:** App. C W/2 E/2 Sec. 35-27-12  
 Pratt County, Kansas  
**COMMENCED:** 8-21-67  
**COMPLETED:** 9-2-67  
**ELEVATION:** 1767 Kelly Bushing

0 - 1560	Shale & Shells	13-3/8" casing set at 164' W/275 ex.
1560 - 1655	Lime & Shale	8-5/8" casing set at 821' W/400 ex.
1655 - 2335	Lime	
2335 - 3450	Shale & Lime	
3450 - 3518	Shale & Sand	
3518 - 3660	Lime & Shale	
3660 - 4095	Lime	5-1/2" casing set at 4068' W/225 ex.
4095 -	T.D.	

LOG TOPS

Heebner	3408 (-1641)
Toronto	3422 (-1655)
Douglas	3440 (-1673)
Douglas Sand	3532 (-1765)
Brown Lime	3598 (-1831)
Lansing	3615 (-1848)
B/Kansas City	3977 (-2210)
Marmaton	4004 (-2237)
Mississippian	4073 (-2306)
LTD	4099

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS        )  
                                   ) SS  
 COUNTY OF SEDGWICK    )

NOV 19 1967

CONSERVATION DIVISION  
Wichita, Kansas

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Barker B#3 located Approximate C W/2 E/2 Section 35-27S-12W Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 8th day of September, 1967.

*Elaine L. Winters*  
Notary Public

My Commission expires May 5, 1970.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 19 1967

CONSERVATION DIVISION  
Wichita, Kansas