

API NUMBER N/A

LEASE NAME BARKER "B"

WELL NUMBER 2

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

990 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 35 TWP. 27S RGE. 12 (E or W)

COUNTY FRA TT

Date Well Completed 2-10-68

Plugging Commenced 10-29-87

Plugging Completed 10-29-87

LEASE OPERATOR Bowers Drilling Co., Inc.

ADDRESS 125 No. Market, Ste. 1425, Wichita, KS. 67202

PHONE # (316) 262-6449 OPERATORS LICENSE NO. 5435

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Lans. KC Depth to Top 3626 Bottom 3991 T.D. 4121

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation  | Content    | From     | To          | Size          | Put In      | Pulled out  |
|------------|------------|----------|-------------|---------------|-------------|-------------|
| <u>LKC</u> | <u>oil</u> | <u>0</u> | <u>156</u>  | <u>13 3/8</u> | <u>156</u>  | <u>0</u>    |
|            |            | <u>0</u> | <u>830</u>  | <u>8 5/8</u>  | <u>830</u>  | <u>0</u>    |
|            |            | <u>0</u> | <u>3977</u> | <u>5 1/2</u>  | <u>3977</u> | <u>1751</u> |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged w/SAND TO 3400' + 6 SAK Cement. Pulled 1751' 5 1/2" Csg. plugged hole WITH 4 SAK HULLS, 100 SAK THIRTY MIX by B.J. 500# SIP

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bowers Drilling Co., Inc. License No. 5435

Address 125 No. Market, Ste. 1425, Wichita, Kans. 67202

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Emil E. Bowers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Emil E. Bowers

(Address) Wichita, Ko.

SUBSCRIBED AND SWORN TO before me this 16th day of February, 1987

My Commission Expires: Judy C. Ridder  
 STATE NOTARY PUBLIC  
 SEDGWICK COUNTY, KANSAS  
 MY APPT. EXP. 3/2/88

JUDY C. RIDDER  
 STATE NOTARY PUBLIC  
 SEDGWICK COUNTY, KANSAS  
 MY APPT. EXP. 3/2/88

RECEIVED  
 STATE CORPORATION COMMISSION  
 RECEIVED  
 STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
 Wichita, Kansas  
 NOV 19 1987 Form CP-4  
 Revised 08-84

WELL LOG

**COMPANY:** Bowers Drilling Company, Inc.  
**CONTRACTOR:** Bowers Drilling Company, Inc.  
**FAH:** Barker B02  
**LOCATION:** C N/2-S/2-SE Section 35-278-12W  
 Pratt County, Kansas  
**COMMENCED:** 8-8-67  
**COMPLETED:** 8-17-67  
**ELEVATION:** 1775 Kelly Bushing

|             |                |                                      |
|-------------|----------------|--------------------------------------|
| 0 - 250     | Sand           | Set 13-9/8" casing at 156' W/175 eaz |
| 250 - 836   | Redbed         |                                      |
| 836 - 1500  | Shale & Shells | Set 8-5/8" casing at 838' W/450 eaz  |
| 1500 - 3645 | Lime & Shale   |                                      |
| 3645 - 4023 | Lime           |                                      |
| 4023 - 4120 | Lime & Chert   |                                      |
| 4120 -      | T.D.           |                                      |

LOG TOPS

|               |      |       |
|---------------|------|-------|
| Heebner       | 3422 | -1647 |
| Toronto       | 3436 | -1661 |
| Douglas       | 3454 | -1679 |
| Brown Lime    | 3608 | -1833 |
| Lansing       | 3626 | -1851 |
| B/Kansas City | 3991 | -2216 |
| Marmaton      | 4020 | -2245 |
| Mississippian | 4072 | -2297 |
| LTD           | 4121 | -2346 |

STATE OF KANSAS        )  
                                   ) 83  
 COUNTY OF SEDGWICK    )

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 19 1987

I, Emil R. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Barker B02 located C N/2-S/2-SE of Section 35-278-12W Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil R. Bowers*

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 17th day of August, 1967.

*Elaine L. Winter*  
Notary Public

My Commission expires May 5, 1970.

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 19 1987

CONSERVATION DIVISION  
 Wichita, Kansas