

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1650 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 35 TWP. 27S RGE. 12 (E) or (W)

COUNTY PRATT

Date Well Completed 8-28-67

Plugging Commenced 10-29-87

Plugging Completed 10-29-87

LEASE OPERATOR Bowers Drilling Co., Inc.

ADDRESS 125 No. Market, Suite 1425, WICHITA, Ks. 67202

PHONE (316) 262-6449 OPERATORS LICENSE NO. 5435

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation LANS. KC Depth to Top 3620 Bottom 3983 T.D. 4387

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>LKC</u>	<u>oil</u>	<u>0</u>	<u>151</u>	<u>13 3/8</u>	<u>151</u>	<u>0</u>
		<u>0</u>	<u>835</u>	<u>8 5/8</u>	<u>835</u>	<u>0</u>
		<u>0</u>	<u>4143</u>	<u>4 1/2</u>	<u>4143</u>	<u>2500</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged Csg. w/ sand to 3650' + 45% cement. Pulled 2500' 4 1/2" Csg. + plugged hole with 100% Thrifty Mix Cement by B.I. 500# SIP

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bowers Drilling Co., Inc. License No. 5435

Address 125 No. Market, WICHITA, KANS. 67202

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Emil E. Bowers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Emil E. Bowers

(Address) WICHITA, Ks.

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1987

Judy C. Ridder
 Notary Public

My Commission Expires:

JUDY C. RIDDER
 STATE NOTARY PUBLIC
 SEDGWICK COUNTY, KANSAS
 MY APPT. EXP. 3/2/88

RECEIVED
 STATE CORPORATION COMMISSION

NOV 19 1987

Form CP-4
 Revised 08-84

WELL LOG

COMPANY: Bowers Drilling Company, Inc.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: Barker B#1
 LOCATION: C S/2 NW SE Section 35-27S-12W
 Pratt County, Kansas
 COMMENCED: 6-24-67
 COMPLETED: 7-7-67
 ELEVATION: 1776 Kelly Bushing

0 - 145 Sand & Soil
 145 - 250 Red Bed Set 13-3/8' at 151' W/200 sx.
 250 - 640 Red Bed, Shale & Shells
 640 - 840 Red Bed Set 8-5/8 at 835' W/400 sx.
 840 - 1550 Cement
 1550 - 3640 Lime & Shale
 3640 - 4107 Lime
 4107 - 4138 Lime & Chert
 4138 - 4190 Lime
 4190 - 4277 Shale Set 4-1/2' at 4143' W/150 sx.
 4277 - 4335 Lime
 4335 - 4387 Shale & Sand
 4387 - T.D.

LOG TOPS
 Topeka 3061
 Heebner 3414
 Toronto 3428
 Douglas Shale 3445
 Brown Lime' 3602
 Lansing 3620
 B/Kansas City 3983
 Karmaton 4013
 Mississippian 4063
 Kinderhook Shale 4192
 Viola 4254
 Simpson Shale 4338
 Simpson Sand 4344
 LTD 4388

RECEIVED
 STATE CORPORATION COMMISSION

NOV 19 1987

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Barker B#1 located C S/2 NW SE of Section 35-27S-12W, Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Subscribed and sworn to before me, a Notary Public, in and for Sedgewick County, Kansas this 11th day of July, 1967.

RECEIVED
 STATE CORPORATION COMMISSION

NOV 19 1987

CONSERVATION DIVISION
 Wichita, Kansas

My Commission expires May 5, 1970.