

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,577-00-00

LEASE NAME Barker

WELL NUMBER A-1

SPOT LOCATION NW/4 NE/4 SE/4

SEC. 34 TWP. 27 RGE. 12 (E) or (W) (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 2-24-86

Plugging Completed 3-3-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D & D Productions, Inc.

ADDRESS P.O. Box 321 Pratt, Kansas 67124

PHONE # (316) 672-5002 OPERATORS LICENSE NO. 9514

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.O. 4595'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	400'	none
				5-1/2"	4571'	3169'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3760' and 5 sacks cement. Shot casing @3169' and pulled a total of 73 joints (3169') of 5-1/2" casing. Plugged surface with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 150 cement, 60/40 pos, 6% gel. Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso


(employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.
(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1986

Irene Hoover
Notary Public

My Commission expires:



MAR 18 1985

D & D DRILLING
 D & D PRODUCTION, INC.
 Producers of Oil and Gas
 403 S. Main, P. O. Box 321
 Pratt, KS 67124
 (316) 672-5002

DRILLER'S WELL LOG

Barker A-1
 NW NE SE 34-27-12
 Pratt County, Kansas
 Commenced: 2-15-85
 Completed: 3-18-85
 API# 15-151-21,577
 Operator: D & D Production, Inc.

<u>Depth</u>	<u>Formation</u>	<u>Remarks</u>
0 - 354	Sand, Clay, Shale	Ran 9 joints, new, 24#,
354 - 1930	Shale	8 5/8" surface casing. Set
1930 - 3488	Heebner	at 392' with 284 sxs
3488 - 3500	Toronto	60/40 poz, 2% gel, 3% cc.
3500 - 3500	Douglas	Job by Buie Co. Plug down
3500 - 3678	Brown Lime	at 11:30 a.m. 2-16-85.
3678 - 3692	Lansing	
3692 - 4056	Base Kansas City	RTD 4595
4056 - 4086	Marmaton	
4086 - 4155	Mississippian	Ran 106 joints, new 15.5#,
4155 - 4278	Kinderhook	5.5" production casing.
4278 - 4333	Viola	Set at 4571' with 250 sxs
4333 - 4370	Simpson Dolomite	60/40 poz. Job by Allied.
4370 - 4440	Simpson Shale	Plug down at 8:25 p.m.
4440 - 4444	Simpson Sand	2-28-85.
4444 - 4537	Arbuckle	
4537 - 4595	RTD/LTD	

RECEIVED
 STATE CORPORATION COMMISSION

MAR 11 1985

CONSERVATION DIVISION
 Wichita Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

D & D DRILLING, a division of
 D & D PRODUCTION, INC.

Darrel Anderson
 Darrel Anderson, President

Christine E. Davis
 NOTARY PUBLIC

