

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt

County. Sec. 4 Twp. 27S Rge. (E) 13 (W)

Location as "NE/CNW&SW&" or footage from lines Ctr. E/2 NE/4 NW/4

Lease Owner Monsanto Chemical Company

Lease Name Chance Well No. 4

Office Address P. O. Box 580, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed January 29, 19 47

Application for plugging filed February 6, 19 58

Application for plugging approved February 7, 19 58

Plugging commenced February 15, 19 58

Plugging completed February 15, 19 58

Reason for abandonment of well or producing formation Production Depleted

If a producing well is abandoned, date of last production June 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Lackamp

Producing formation Viola Depth to top 4306 Bottom 4359 Total Depth of Well 4464 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	802'	802' None
				5-1/2"	4458'	4458' None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand from 4340' to 4292', 5 sacks of cement on top of sand.
Heavy mud to 350', rock plug @ 350' with 20 sacks of cement
on top of plug. Heavy mud to 35', rock plug @ 35' with 10
sacks of cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS COUNTY OF PRATT ss.
Bruce E. Roll (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce E. Roll
P. O. Box 580, Pratt, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of February, 19 58

My commission expires September 19, 1959 Notary Public.

PLUGGING
FILE SEC 4 T 27 R 13 W
BOOK PAGE 81 LINE 9

Lion Chemical Corporation
El Dorado, Arkansas

Chance Well No. 4

E/2 of NE NW
Section 4-27S-13W
Pratt County, Kansas

Contractor: The R. W. Rine Drilling Company
Started: 1-9-47 Finished: 1-29-47

LOG

Sand, clay and red bed	0 - 167	
Sand and red bed	167 - 560	
Shale and shells	560 - 805	8-5/8" casing @ 802'
Shale and shells	805 - 900	
Sand, shells and shale	900 - 1554	
Shale and shells	1554 - 1800	
Shale and lime	1800 - 1980	
Shale and shells	1980 - 2305	
Lime and shale	2305 - 3520	
Shale	3520 - 3605	
Lime and shale	3605 - 3720	
Lime	3720 - 3785	
Lime and shale	3785 - 3919	
Lime	3919 - 3983	
Lime and shale	3983 - 4199	
Lime	4199 - 4340	
Lime and shale	4340 - 4347	
Sand	4347 - 4352	
Sand and shale	4352 - 4373	
Lime and shale	4373 - 4430	
Shale	4430 - 4438	
Lime	4438 - 4460	5-1/2" casing cemented @ 4458'

TOTAL DEPTH: 4460'

State of Kansas)
County of Pratt) ss


I, Bruce E. Roll, do hereby certify that to the best of my knowledge the above is a true and complete log of the Chance Well No. 4 located in the E/2 of NE/4 of the NW/4 of Section 4-27S-13W in Pratt County, Kansas.

Bruce E. Roll

Sworn to and subscribed before me this 19th day of March, 1958.

Merle A. Lindsay
Notary Public

My commission expires September 19, 1959



RECEIVED
STATE CORP.

MAR 21 1958

CONSERVATION DIVISION
Wichita, Kansas