

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County. Sec. 5 Twp. 27 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SW NE SE 4
Lease Owner Max Cohen
Lease Name Phillips Well No. 1
Office Address Brown Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed May 17, 19 53
Application for plugging filed May 17, 19 53
Application for plugging approved May 17, 19 53
Plugging commenced May 17, 19 53
Plugging completed May 17, 19 53
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4511 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	870'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole full of heavy Rotary Mud to 300 ft.,
set plug and run 20 sacks of cement through drill
pipe. Mudded hole to 40 ft., set plug and run 10 sacks
cement to surface.

STATE CORPORATION COMMISSION
JUN 17 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M. B. Armer
Address 710 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg Employee of Contractor
(employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 19 53

My commission expires February 13, 1956

24-7366-5 3-53-20M

PLUGGING
FILE SEC 5 T 27 R 13a
DATE 10/21/53

Notary Public.

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Max Cohen**

SEC. **5** T. **27S** R. **13W**

FARM **Phillips**

NO. **1**

LOC. **SW NB 6E**


TOTAL DEPTH **4511**

COUNTY **Pratt**

COMM. **4/27/53**

COMP. **5/18/53**

SHOT OR TREATED
CONTRACTOR **H. D. ARMER**



ISSUED

CASING

20	10	
15	8	697'
12	6	
13	5	

ELEVATION **1966 K.F.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	210
Red Red & Shells	455
Shale & Sand	510
Shale & Shells	565
Red Red, Shells & Shale	800
Red Red & Shells	1110
Shale, Shells & Salt	1590
Shale & Shells	1885
Line, Shale & Shells	2005
Line & Shale	2650
Shale & Shells	2790
Line & Shale	2930
Shale & Shells	3100
Line & Shale	3190
Shale & Shells	3280
Shale & Line	3375
Line	3420
Broken Line	3510
Shale & Line	3755
Line	3928
Line & Shale	3980
Line	4205
Chert Line	4225
Cherty Line & Shale	4250
Chert Line	4295
Cherty Line & Shale	4307
Chert & Line	4318
Chert	4368
Line & Shale	4373
Simpson	4439
Shale - hard	4506
Arbuckle	4511

FORMATION TOPS

(R. E. Meas.)

TOPEKA	3277
HERRIN	3617
BROWN LINE	3790
LAISING	3808
BASE KANSAS CITY	4137
CONGLOMERATE	4220
MISSISSIPPI LINE	4231
KIMBERHOOK	4264
VIOLA	4311
SIMPSON	4370
ARBUCKLE	4500

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H. D. ARMER

RECEIVED
STATE GEOLOGICAL SOCIETY
JUN 17 1953

[Signature]

STATE OF KANSAS
COUNTY OF SEDGWICK

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me, a notary public, in and for said County and State this 19th day of May, 1953.

Rose Lurey
Notary Public

My Commission Expires: Feb. 13, 1956.

PLUGGING
FILE SEC 2-27 R 13W
BOOK PAGE 102 LINE 9