

CARDS MUST BE TYPED

STATE OF KANSAS  
NOTICE OF INTENTION TO DRILL

C-1  
M-1331

TO BE FILED WITH THE STATE CORPORATION COMMISSION  
5 DAYS PRIOR TO COMMENCEMENT OF THIS PERMIT

API Number 15- 047-21,047-0000  
(For office use only)

Starting Date 6 / 10 / 1982  
Month Day Year

County EDWARDS

Sec. 7 Twp. 24 S. Rng. 16  East  West

Exact Spot Location of Well NE SW NW

Nearest Lease Line 990

Lease Name HAWLEY

Well No. 7-7

Est. Total Depth 4370

**MAILED**

JUN 3 1982

CONSERVATION DIVISION  
WICHITA, KANSAS

OPERATOR STATES THAT HE WILL COMPLY WITH K.S.A. 55-128

1. Operator F. S. G. Holl DEC 02 1982
- Mailing Address 6427 East Kellogg
- Street Address \_\_\_\_\_
- City-State Wichita, Kansas Zip Code 67207
- Contact person Elwyn H. Nagel Phone # 684-8481
2. Contractor Sterling Drilling Company
- Street Address Box 129
- City-State Sterling, Kansas Zip Code 67579
3. Type of Equipment: Rotary  Air  Cable Tools
4. Well to be Drilled for: Oil  Gas  SWD  Input
5. Well Classification: Infield  Pool Ext  Wildcat
6. Depth of Deepest Fresh Water within 1 mile 100 ft.
7. Depth of Municipal Water Well within 3 miles 130 ft.
8. Depth to Protect all Fresh Water (Table 1) 450 ft.
9. Amount of Surface Casing to be set 250 ft.
10. (Surface Casing) Alternate No. 1 \_\_\_\_\_ Alternate No. 2

\$40.00 FEE PAID  67-52

REMARKS: PC 19486

Signature of Operator Elwyn H. Nagel  
Elwyn H. Nagel, Geologist

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1983

CONSERVATION DIVISION  
Wichita, Kansas

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HAWLEY #7-7

Located: NE SW NW, Section 7-24S-16W, Edwards County,  
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 10, 1982

COMPLETED: June 16, 1982

TOTAL DEPTH: 4390'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# new casing. 252.88' pipe set at 265' K.B.
90 - 268 Shale	Cemented with 210 sacks 60/40 Pozmix with 3% cc. Plug down at 10:30 AM, 6-10-82, by Howco.
268 - 1013 Shale and Sand	
1013 - 1098 Shale	
1098 - 1115 Anhydrite	
1115 - 4390 Lime and Shale	Ran 109 joints 4 1/2", 10.5# new casing. 5 joints have been sand blasted. 4374.69' pipe set at 4384' K.B. Cemented with 100 sacks Lite, and 125 sacks 50/50 Pozmix plus regular additives. Plug down at 1:15 PM, 6-16-82, by Howco. Pulled water well, plugged with 5 sacks. Plugged rathole with 10 sacks.

Deviation Surveys: 1° at 2260'

1° at 4302'  
**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 28 1983

CONSERVATION DIVISION  
Wichita, Kansas