

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-01203-00-00
Spot: SW Sec/Twnshp/Rge: 21-30S-16E
800 feet from S Section Line, 700 feet from W Section Line
Lease Name: UNIT 1 - FEE Well #: CLLEGG #5
County: WILSON Total Vertical Depth: 850 feet

Operator License No.: 3830

Op Name: A X & P, INC.

Address: PO BOX 1176
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	600		
SURF	7	20		This line S/B deleted
SURF	7	30		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/25/2014 9:00 AM

Plug Co. License No.: 33969

Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE

Proposal Rcvd. from: J J HANKE

Company: A X & P, INC

Phone: (620) 325-5212

Proposed
Plugging
Method:

Pull out of hole the rods and tubing. Perforate casing @ 560' 200' and 50'. RIH 1" pipe and Spot Cement and fillup. Fill-up to Surface.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: NONE

Date/Time Plugging Completed: 09/26/2014 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

9-25-2014: The tubing, rods, and pump were removed. The casing was then perforated at 800 ft, 560 ft, 200 ft and 75 ft. Also ran into well 800 ft of 1 inch pipe to be used for cementing. 9-26-2014: Gel was circulated. 10 sacks of cement was spotted at btm. The cement string was raised to 550 ft and 10 sacks of cement spotted. The cement string was raised to 200 ft and the well filled with cement from 200 ft to surface. The 1 inch cement string was removed and the well topped off with cement. A total of 96 sacks of portland cement were used to plug well.

Perfs:

RECEIVED

NOV 07 2014

KCC Chanute Dist. #3

AD

Received
KANSAS CORPORATION COMMISSION

NOV 10 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
11/12/14 CKM

(TECHNICIAN)