

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-141-20031-00-00
Spot: NESESE Sec/Twnshp/Rge: 15-8S-14W
910 feet from S Section Line, 430 feet from E Section Line
Lease Name: BALES Well #: 3
County: OSBORNE Total Vertical Depth: 2861 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2861		150 SX
SURF	8.625	220		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2014 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: LEVI KOEHN Company: BRUCE OIL COMPANY Phone: (620) 241-6426

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
10/22/14- Ordered 350 sx 60/40 pozmix 4% gel cement and 3% C.C. on the side.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2014 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2558' and pumped 100 sx cement w/50 # hulls. Pulled tubing to 1160' and pumped 100 sx cement with no blow on the backside. POOH and shut down for the night.
10/22/2014- Ran tubing in and tagged top of cement at 638'. Pulled up and pumped 45 sx cement. Cement circulated. POOH. Hooked up to casing and pumped 15 sx cement at 300 psi. Shut in. Braden head dug out and pumped 5 sx cement.

GPS: 39.35238 -098.86185

Perfs:

Top	Bot	Thru	Comments
2838	2842		
2809	2813		
2628	2638		

Received
KANSAS CORPORATION COMMISSION

Remarks: QUALITY CEMENTING TICKET # 283,958

Plugged through: TBG

OCT 30 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Ray Dinkel
11/12/14 CKM (TECHNICIAN)

CM

OCT 27 2014