

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-02734-00-00  
Spot: E2NWSE Sec/Twnshp/Rge: 22-14S-14W  
2310 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: G BOXBERGER A&B Well #: 4  
County: RUSSELL Total Vertical Depth: 3079 feet

Operator License No.: 34912  
Op Name: C12 KANSAS OIL, LLC  
Address: 1900 WAZEE ST. SUITE 200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3003		
SURF	8.625	829		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2014 11:00 AM  
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: AVEN WEAVERLING Company: C-12 KANSAS OIL LLC Phone: (785) 623-3221

Proposed Plugging Method: Ordered 250 sx Class A cement w/3% C.C. and 500 # hulls.  
Ordered 300 sx 60/40 pozmix 4% gel cement 1/4# sx flo-sel  
Cement retainer

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/15/2014 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2600' and pumped 50 sx Class A cement w/300 # hulls. POOH. Ran and set cement retainer at 2250'. Ran tubing and hooked in to retainer. Pumped 100 sx Class A cement at 700 psi. POOH. Perforated casing at 1450', 860' and 350'. Ran tubing to 1600' and tagged cement. Pulled one joint and pumped 40 sx cement. Pulled tubing to 1240' and pumped 100 sx cement. Had cement circulating out braden head and in cellar. Shut in.

GPS: 38.81822 -098.86059

Perfs:

Top	Bot	Thru	Comments
3069	3079		
3019	3024		

Remarks: QUALITY CEMENTING TICKET # 769

Plugged through: TBG

Received  
KANSAS CORPORATION COMMISSION

OCT 30 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

11/12/14 CKM

OCT 24 2014