

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-21345-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 19-20S-5W
3009 feet from S Section Line, 1973 feet from E Section Line
Lease Name: ENOCHS Well #: 1
County: MCPHERSON Total Vertical Depth: 3385 feet

Operator License No.: 4184
Op Name: CASINO PETROLEUM, LLC
Address: PO BOX 415
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2680		
PROD	5.5	3365		125 SX
SURF	8.625	295		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2014 1:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JIM LYMAN Company: D S & W WELL SERVICING, INC. Phone: (620) 786-4258

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/22/2014 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND BOTTOM PERFS TO 3200' AND CAP WITH 5 SX'S CEMENT. SET 5.5" @ 2680' AND CAP WITH 2 SX'S CEMENT. SHOOT CASING OFF @ 1938' AND PULL TO 800' AND PUMP 35 SXS CEMENT. PULL CASING UP TO 430' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3287	3294		

Received
KANSAS CORPORATION COMMISSION
NOV 10 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #8233. COPELAND CEMENT #42391.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

11/12/14 ccm