

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-00616-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 10-30S-8W  
2280 feet from N Section Line, 351 feet from E Section Line  
Lease Name: MORRIS KB Well #: 2  
County: KINGMAN Total Vertical Depth: 4184 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4154		
PROD	5.5	4155		50 SX
SURF	8.625	219		130 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/15/2014 12:00 AM

Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: PAUL Company: CITATION OIL & GAS CORP. Phone: \_\_\_\_\_

Proposed Plugging Method: CIBP 4100 & 2 SXS. 50 SXS 1500'. 50 SXS @ 720'. CIRCULATE 300'-0'.

Plugging Proposal Received By: \_\_\_\_\_

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/29/2014 4:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4100' & 2 SXS CEMENT. PERF CASING @ 1500'. SET CEMENT RETAINER 1450'. STRING INTO RETAINER & PUMPED 50 SXS CEMENT. PULLED TUBING TO 720' PUMPED 50 SXS CEMENT. TAGGED PLUG - NOTHING. PUMPED 50 SXS CEMENT. TAGGED 680'. RAN TUBING TO 300' & CIRC'D HOLE.

Perfs:

Top	Bot	Thru	Comments
4155	4184	CSG	

Received  
KANSAS CORPORATION COMMISSION  
NOV 10 2014

Remarks: ALLIED CEMENT COMMON CEMENT 3% CACL

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

*[Handwritten Signature]*  
11/12/14 cpm

(TECHNICIAN)