

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-01604-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 3-9S-19W  
990 feet from N Section Line, 3630 feet from W Section Line  
Lease Name: ROSTOCIL "A" Well #: 2  
County: ROOKS Total Vertical Depth: 3439 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3435		175 SX
SURF	8.625	328		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/08/2014 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL Phone: (785) 259-1928

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Squeezed: 150' - 160' w/60 sx cement, 890' - 925' w/15 sx cement, 1248' - 1407' w/150 sx cement, 1849' - 1881' w/100 sx cement and 2639' - 2670' w/50 sx cement.  
Arbuckle O.H. 3435' - 3439'.  
Production perforations: 3190' - 3385'. Squeezed off 2007 2348' - 2498' w/100 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/08/2014 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2891' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1918' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 893' and pumped 75 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/35 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 1/4 bbl. Pressured to 300 psi.

GPS: 39.29543N -099.43163W

Perfs:

Top	Bot	Thru	Comments
3380	3385		
3345	3347		
3254	3256		
3234	3237		
3207	3210		
3190	3193		
3096	3106		

Received  
KANSAS CORPORATION COMMISSION

OCT 30 2014

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED TICKET # 55515

Plugged through: TBG

District: 04

Signed

Pat Bedore  
11/12/14 cm (TECHNICIAN)

CM