

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-01018-00-01
Spot: SESENW Sec/Twnshp/Rge: 2-18S-14W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: TINDALL OWWO Well #: 3
County: BARTON Total Vertical Depth: 3409 feet

Operator License No.: 7023
Op Name: KLIMA WELL SERVICE, INC.
Address: PO BOX 48
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3348		
SURF	8.625	816		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2014 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KILMA Company: KLIMA WELL SERVICE, INC. Phone: (620) 793-8888

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2014 6:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 3180' and pumped 50 sx cement w/100 # hulls. Pulled tubing. Shut down for the day. Tied to casing to start pulling casing. Casing parted at 380' at collar in casing. Tried to screw casing back and couldn't. Pulled casing and tried to run tubing into casing. Could not get tubing into casing. Ran back in with casing with overshot and got back on the casing. Ran in perf gun and perforated at 1450' and 800'. Ran tubing to 1450' and pumped 50 sx cement. Pulled casing to 800' and pumped 40 sx cement. Pulled tubing. Pulled 1 joint of casing to 350'. Circulated cement to surface with 100 sx cement. Pulled casing and topped off with 15 sx cement.

GPS: 38.51495 -098.84061

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

OCT 30 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Bruce Rodie

11/12/14 ckm

(TECHNICIAN)

CM

OCT 24 2014