

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-16571-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 2-18S-14W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: EVELEIGH Well #: 2
County: BARTON Total Vertical Depth: 3357 feet

Operator License No.: 7023
Op Name: KLIMA WELL SERVICE, INC.
Address: PO BOX 48
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3349		0 SX
SURF	10.75	807		450 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2014 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE, INC. Phone: (620) 793-8888

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 18 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2014 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450' and 820'.
Ran tubing to 3200' and pumped 18 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 110 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 400'. Circulated cement to surface on casing w/180 sx cement. Pulled tubing. Tied to casing and circulated cement on backside w/60 sx cement.

GPS: 38.50953 -098.84296

Perfs:

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

OCT 30 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

11/12/14 ckm

OCT 25 2014