

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22925-00-02
Spot: NWSWSW Sec/Twnshp/Rge: 6-7S-20W
1050 feet from S Section Line, 4920 feet from E Section Line
Lease Name: R V JONES Well #: 1
County: ROOKS Total Vertical Depth: 3720 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3716		125 SX
SURF	8.625	214		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2014 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/450 # hulls.
Port collar at 1774' w/385 sx cement.
Production perforations: 3387' - 3664'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2014 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3630' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 2400' and pumped 150 sx cement w/150 # hulls. Pulled tubing to 800' and pumped 80 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus. Pressured to 300 psi immediately.

GPS: 39.46946N -099.60064W

Perfs:

Top	Bot	Thru	Comments
3455	3457		
3436	3439		

Received
KANSAS CORPORATION COMMISSION

Remarks: ALLIED TICKET # 55517

Plugged through: TBG

OCT 30 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

11/12/14 CKM

Form CP-2/3

OCT 16 2014