

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22958-00-02
Spot: NWSESW Sec/Twnshp/Rge: 6-7S-20W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: R V JONES Well #: 2
County: ROOKS Total Vertical Depth: 3720 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3689		125 SX
SURF	8.625	218		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2014 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.
1780' w/475 sx
Production perforations: 3420' - 3627'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2014 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3550' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2400' and pumped 100 sx cement w/50 # hulls to circulate cement to surface. Pulled all tubing. Hooked to 4 1/2" casing and pumped 25 sx cement. Shut in pressure 200 psi. Hooked to 8 5/8" x 4 1/2" annulus and pumped 5 sx cement. Backside standing full.

GPS: 39.46936N -099.59694W

Perfs:

Top	Bot	Thru	Comments
3624	3627		
3475	3477		
3469	3672		
3420	3422		

Remarks: ALLIED TICKET # 55340

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

OCT 30 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Pat Bedore

11/12/14 okm (TECHNICIAN)

(M)

OCT 16 2014