

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23026-00-01  
Spot: SENESEW Sec/Twnshp/Rge: 6-7S-20W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: R V JONES Well #: 3  
County: ROOKS Total Vertical Depth: 3720 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3710		125 SX
SURF	8.625	212		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Port collar at 1785' w/300 sx cement. Production perforations: 3417' - 3516'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/07/2014 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3650' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2400' and pumped 100 sx cement. Pulled tubing to 1200' and pumped 90 sx cement to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/ 10 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 1 sx cement. Shut in pressure 150 psi.

GPS: 39.47114N -099.59456W

Perfs:

Top	Bot	Thru	Comments
3417	3420		

Received  
KANSAS CORPORATION COMMISSION

Remarks: CONSOLIDATED TICKET # 47713

Plugged through: TBG

**OCT 30 2014**

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

11/12/14 ckm

CM

OCT 16 2014

Form CP-2/3