

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24253-00-00
Spot: NWSENEW Sec/Twnshp/Rge: 5-9S-20W
1786 feet from S Section Line, 2291 feet from W Section Line
Lease Name: ROBERTS Well #: 1
County: ROOKS Total Vertical Depth: 3770 feet

Operator License No.: 32322

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	230		

Op Name: ROBERTS, DENIS F.

Address: 3904 FAIRWAY DR BOX 1252
HAYS, KS 67601

Well Type: DH

UIC Docket No:

Date/Time to Plug: 10/07/2014 12:00 AM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Revd. from: TOM

Company: DISCOVERY DRILLING

Phone: (785) 623-2920

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS

WitnessType: NONE

Date/Time Plugging Completed: 10/07/2014 6:15 AM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @1680 w/50 sx
2nd plug @875 w/100 sx
3rd plug @300 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

Received
KANSAS CORPORATION COMMISSION

OCT 30 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Case Morris
11/12/14 CCM (TECHNICIAN)

OCT 16 2014