

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-04337-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 35-23S-4E
4913 feet from S Section Line, 4974 feet from E Section Line
Lease Name: HARVEY Well #: 7
County: BUTLER Total Vertical Depth: 2150 feet

Operator License No.: 34569
Op Name: SONOMA RESOURCES LLC
Address: PO BOX 384
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2140		50 SX
SURF	8.625	160		130 SX

Well Type: EOR UIC Docket No: E10457.1 Date/Time to Plug: 07/14/2014 8:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DAN FLOWERS Company: SONOMA RESOURCES, LLC. Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS/ 15 SXS, TAG TO 2050', PERF @ 280' & CIRC TO SURFACE.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 07/15/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2140', CONSOLIDATED OILWELL SERVICE MIXED & PUMPED 35 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1760', RIH ON WIRELINE SHOT SQUEEZE HOLES @ 250'-251'. RIH W/TBG @ 250', CONSOLIDATED OILWELL SERVICE MIXED & PUMPED 85 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. NO CEMENT TICKET #.

Perfs:

Top	Bot	Thru	Comments
2140	2150	OH	

Received
KANSAS CORPORATION COMMISSION
NOV 10 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: SHOWED SIGNS OF CEMENT @ SURFACE ON BACKSIDE OF 4.5" CSG, FAILED MIT/ COMPLIANCE

Plugged through: TBG

District: 02

Signed

Duane Krueger

cc:ulc
11/12/14 ckm

(TECHNICIAN)

1/5K