

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-20468-00-00
Spot: SW Sec/Twnshp/Rge: 2-22S-37W
1334 feet from S Section Line, 3933 feet from E Section Line
Lease Name: PEARL Well #: 1
County: KEARNY Total Vertical Depth: 3100 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2865		WITH 2 SX CMT
CIBP		3099		
PROD	5.5	3100	0	WITH 550 SX CMT
SURF	8.625	333		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/24/2014 11:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2014 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2865' WITH 2 SX CMT. RAN CBL FROM 1700' TO 0'. TOC @ 480'.
PERFORATE 4 HOLES AT 380'. RUN TBG TO 2125'. SPOT 150 SX CMT INSIDE
CASING UP TO 400'. TOOH WITH TBG & HOOK TO 5 1/2" CASING. CIRCULATE
CMT TO SURFACE THROUGH PERFS AT 380' USING 125 SX CMT LEAVING THE
CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2914	2986		

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

RECEIVED
NOV 13 2014
KCC DODGE CITY

Signed

Ken Jehlik
(TECHNICIAN)

12/4/14 CKM

ST