

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00765-00-00
Spot: E2 Sec/Twnshp/Rge: 16-23S-32W
2707 feet from S Section Line, 1320 feet from E Section Line
Lease Name: E Well #: 1
County: FINNEY Total Vertical Depth: 2694 feet

Operator License No.: 30269
Op Name: ARGENT ENERGY, INC.
Address: 1313 N WEBB RD STE 210
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1150		
CIBP		1740		
PROD	5.5	2694	0	WITH 600 SX CMT
SURF	8.625	369		WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/06/2014 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: EARL OCHAMPAUGH Company: ARGENT ENERGY Phone: (620) 272-1219

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2014 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

of

Perfs:

TAGGED FILL UP AT 1746'. SET CIBP @ 1740'. 8-10 JOINTS/FO TBG WITH 2-3 RODS ABOVE THE TBG LEFT IN HOLE. SET CIBP @ 1150'. TEST CASING TO 750#. HOLDING. PERFORATE 4 HOLES AT 1100'. INJECTION RATE 2 BPM @ 1300 PSI. PUMP 80 SX CMT AT 1000#-1300# & DISPLACE LEAVING 1/2 THE CMT OUT THE PERFS AND 1/2 THE CMT INSIDE THE CASING. PERFORATE 4 HOLES AT 400'. ATTEMPT TO PUMP INTO AT 1000#. COULD NOT. RUN TBG TO 404' & CIRCULATE CMT TO SURFACE WITH 50 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS TO 250#.

Top	Bot	Thru	Comments
2652	2661		
2610	2616		
2588	2596		

Received
KANSAS CORPORATION COMMISSION
DEC 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

12/4/14 CKM

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED

NOV 19 2014

KCC DODGE CITY

Form CP-2/3

KMS