

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-20791-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 7-35S-26W
4020 feet from S Section Line, 3588 feet from E Section Line
Lease Name: MARY SUTHERLAND Well #: 1-7
County: MEADE Total Vertical Depth: 6600 feet

Operator License No.: 34274
Op Name: BALLOUN, VIOLETTE DBA HI-KAT PE
Address: 1410 N PROSPECT PO BOX 1261
LIBERAL, KS 67901

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6100		WITH 2 SX CMT
CIBP		6400		
COND	20	80		
PROD	4.5	6598	2100	WITH 200 SX CMT
SURF	8.625	566		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/20/2014 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580)254-1881

Proposed Plugging Method: SET CIBP @ 6100' WITH 2 SX CMT. PLUG AT 1310' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 11/20/2014 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 6100' WITH 2 SX CMT. LOADED HOLE WITH MUD. 1ST PLUG AT 1310' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT CIRCULATED & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
6492	6500		
6174	6187		
6154	6166		

Received
KANSAS CORPORATION COMMISSION
DEC 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
NOV 21 2014

Signed Kenny Sullivan
(TECHNICIAN)

12/4/14 CKM

KCC DODGE CITY