

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-071-20208-00-00  
Spot: SW Sec/Twnshp/Rge: 21-19S-40W  
1296 feet from S Section Line, 3920 feet from E Section Line  
Lease Name: VOGT Well #: 1  
County: GREELEY Total Vertical Depth: 2965 feet

Operator License No.: 7271  
Op Name: BARTLING OIL COMPANY  
Address: 1001 CANYON EDGE DR  
AUSTIN, TX 78733

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2965	0	WITH 550 SX CMT
SURF	8.625	280		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/13/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GUS OSCHNER Company: BARTLING OIL Phone: (620) 376-2249

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/13/2014 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 200# HULLS TO 2904'. DISPLACE WITH WATER TO 1500'. RUN BOND LOG FROM 1430' TO 50'. TOC @ 96'. RUN TBG TO 1440' & CIRCULATE CMT TO SURFACE IN 2 STAGES WITH 110 SX CMT. TOO H & TOP OFF 4 1/2" CASING WITH 10 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2901	2904		
2889	2896		
2886	2886		

Received  
KANSAS CORPORATION COMMISSION  
DEC 03 2014  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

12/4/14 CCM

District: 01

Signed

*Ken Jehlik*

(TECHNICIAN)

RECEIVED

NOV 19 2014

KCC DODGE CITY

Form CP-2/3

KMS