

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20211-00-00
Spot: NE Sec/Twnshp/Rge: 29-19S-40W
3913 feet from S Section Line, 1324 feet from E Section Line
Lease Name: ALPERS Well #: 1
County: GREELEY Total Vertical Depth: 2970 feet

Operator License No.: 7271
Op Name: BARTLING OIL COMPANY
Address: 1001 CANYON EDGE DR
AUSTIN, TX 78733

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2960	0	WITH 400 SX CMT
SURF	8.625	289		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/14/2014 8:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GUS OSCHNER Company: BARTLING OIL Phone: (620) 376-2249

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2014 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 200# HULLS TO 2920'. DISPLACE WITH WATER TO 1270'. TEST CASING TO 700#. HOLDING. RUN CBL FROM 1480' TO 40'. TOC @ 340'. PERFORATE 4 HOLES AT 300'. BREAK CIRCULATION WITH WATER. RUN TBG TO 1440'. CIRCULATE CMT TO SURFACE IN 2 STAGES USING 110 SX CMT. CIRCULATE CMT UP THE ANNULUS TO SURFACE FROM THE PERFS AT 300' WITH 40 SX CMT. TOP OFF THE 4 1/2" CASING WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2915	2920		
2906	2911		
2900	2901		

Received
KANSAS CORPORATION COMMISSION
DEC 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED

NOV 19 2014

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

12/4/14 CCM

KMS