

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20312-00-02
Spot: N2S2SW Sec/Twnshp/Rge: 25-30S-43W
990 feet from S Section Line, 3960 feet from E Section Line
Lease Name: ANNIE Well #: 1-25
County: STANTON Total Vertical Depth: 5623 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5265		WITH 2 SX CMT
PROD	5.5	5622	0	WITH 300 SX CMT
SURF	8.625	1511		WITH 750 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/17/2014 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GREG KLAUS Company: BEREN CORPORATION Phone: (316) 722-8650

Proposed Plugging Method: SET CIBP @ 5265' WITH 2 SX CMT. CASING LEAK WAS SQUEEZED AT 2000' WITH 175 SX CMT. RUN CBL TO DETERMINE PLUGGING ORDERS.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2014 12:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5265' WITH 2 SX CMT. CASING LEAK WAS SQUEEZED AT 2000' WITH 175 SX CMT. BOND LOG SHOWED TOC @ 930'. RTIH TO 1550' WITH 40 SX CMT. PEROFRATE AT 600' WITH 210 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
5315	5323		

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Kenny Sullivan
CKM 12/4/14 (TECHNICIAN)
[Signature]

RECEIVED

NOV 20 2014

KCC DODGE CITY