

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20994-00-00
Spot: SWSENE Sec/Twnshp/Rge: 13-25S-32W
3019 feet from S Section Line, 1007 feet from E Section Line
Lease Name: HICKS Well #: 2-13
County: FINNEY Total Vertical Depth: 5100 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3062	0	WITH 375 SX CMT
SURF	8.625	1914		WITH 900 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/06/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

PUMP 30 SX CMT WITH 200# HULLS TO 2574'. DISPLACE WITH WATER TO 1950'. TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 1950'. SPOT 50 SX CMT 1/2 IN & 1/2 OUT OF THE 4 1/2" CASING WITH HULLS IN THE LAST 25 SX CMT. PRESSURED TO 250#. HOLDING. PERFORATE 4 HOLES AT 1050' & CIRCULATE CMT TO SURFACE USING 230 SX CMT LEAVING THE 4 1/2" CASING AND THE 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Received
KANSAS CORPORATION COMMISSION
DEC 03 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

12/4/14 cpm

District: 01

RECEIVED
NOV 19 2014
KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

Form CP-2/3

KMS