

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21563-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 14-20S-6W
981 feet from S Section Line, 2334 feet from E Section Line
Lease Name: CASAD-JOHNSON Well #: 1
County: RICE Total Vertical Depth: 3367 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3100		
PROD	5.5	3367		125 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2014 12:00 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: KEITH BRIGHT Company: CMX, INC. Phone: (785) 822-8062

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 11/14/2014 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU CK BOTTOM. SET CIBP @ 3100' AND CAP WITH 5 SX'S CEMENT THRU TUBING. PULL TUBING OUT AND PERFORATE @ 850', 450' AND 250'. RUN IN TUBING AND PACKER TO 850' AND PUMP 35 SX'S CEMENT, PULL TUBING AND PACKER TO 450' AND PUMP 35 SX'S CEMENT PULL TUBING AND PACKER TO 250' AND CIRCULTE CEMENT TO SURFACE. PULL TUBNIG AND PACKER OUT, RUN OPEN ENDED TUBING BACK IN TO 250' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Received
KANSAS CORPORATION COMMISSION
DEC 01 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60/40 POZ. 4% GE./ NABORS PERF TICKET #26192. BASIC SERVICES CEMENT #11441.

Plugged through: TBG

12/4/14 *CPM*

District: 02

Signed Virgil Clothier
(TECHNICIAN)

✓ SK